Najd Gate Mixed-Use Tower

Bill of Quantities - Phase 2

Bill No. 4 - Facade Package: podium feature facade, tower crown and entrances

Revision 0 | Issued 14 September 2026 | Contract No. NGT-MW-2026-001

Prepared by Dune Line Engineering Consultants for Sarab Crest Real Estate Development Company

All rates and amounts are in Saudi Riyals (SAR) and exclude Value Added Tax.

Rates include supply, fabrication, delivery, installation, fixings, testing and protection. Quantities are measured net from the Drawings.

The total of this Bill is carried to the Phase 2 Summary.

Item	Description	Unit	Qty	Rate (SAR)	Amount (SAR)
4.1	**PODIUM FEATURE FACADE (GROUND TO LEVEL 4)**				
4.1.01	Natural granite cladding, 40 mm thick, flamed finish, fixed on stainless steel brackets and an aluminium subframe, including anchors, cutting and drilling	m2	6,850	1,180.00	8,083,000.00
4.1.02	Glass fibre reinforced concrete (GRC) feature screens, 25 mm thick, geometric pattern inspired by traditional mashrabiya, on galvanised steel frames, including fixings	m2	3,240	1,465.00	4,746,600.00
4.1.03	Shopfront glazing to retail units, 12 mm toughened laminated glass in structurally glazed aluminium frames	m2	2,180	1,320.00	2,877,600.00
4.1.04	Aluminium soffit panels to the podium overhang, 3 mm, powder coated	m2	1,140	545.00	621,300.00
4.1.05	Aluminium louvre screens to the podium car park ventilation openings, powder coated, with insect mesh	m2	1,460	640.00	934,400.00
4.1.06	Stainless steel feature trims to window heads and jambs	m	3,950	185.00	730,750.00
4.1.07	Mineral wool insulation, 100 mm thick, behind the cladding	m2	6,850	48.50	332,225.00
4.1.08	Fire barriers at slab edges and cavity closers at every floor	m	2,240	96.00	215,040.00
4.1.09	Breather membrane and vapour control layer behind the cladding	m2	6,850	22.75	155,837.50
4.2	**TOWER CROWN (LEVEL 26 TO ROOF)**				
4.2.01	Structural steel framing to the crown, grade S355, including connections, shop primer and intumescent coating for 90 minutes fire resistance	t	418	9,850.00	4,117,300.00
4.2.02	Laminated glass fins, 2 x 12 mm heat-strengthened glass, 6 m high, with stainless steel shoes and silicone joints	nr	264	4,780.00	1,261,920.00
4.2.03	Perforated aluminium panels to the crown screen, 3 mm, with a backlit pattern	m2	1,920	495.00	950,400.00
4.2.04	Crown access walkways, galvanised steel grating with safety rails	m	380	1,150.00	437,000.00
4.2.05	Architectural lighting to the crown: linear LED fittings, DMX controllers, drivers and cabling, complete	item	1	1,000,000.00	1,000,000.00
4.2.06	Lightning protection bonding to the crown steelwork	item	1	86,500.00	86,500.00
	Carried forward				**26,549,872.50**

Item	Description	Unit	Qty	Rate (SAR)	Amount (SAR)
	Brought forward				**26,549,872.50**
4.3	**ENTRANCES AND CANOPIES**				
4.3.01	Main entrance canopy, 18 m x 9 m, cantilevered steel structure with laminated glass roof, including drainage and lighting	item	1	1,685,000.00	1,685,000.00
4.3.02	Automatic revolving doors, three-wing, 2.4 m diameter, with night shutters	nr	4	186,500.00	746,000.00
4.3.03	Automatic sliding doors, frameless glass, with safety sensors	nr	8	42,800.00	342,400.00
4.3.04	Secondary entrance canopies, aluminium with polycarbonate roof	nr	3	128,000.00	384,000.00
4.3.05	Frameless glass balustrade to podium terraces, 1.1 m high	m	420	1,240.00	520,800.00
4.3.06	Entrance matwells with stainless steel frames	nr	12	6,450.00	77,400.00
4.3.07	Backing panels for building signage at the entrances	m2	96	1,350.00	129,600.00
4.4	**EXTERNAL SHADING AND SCREENS**				
4.4.01	Vertical aluminium fins, 450 mm deep, to the west and south elevations of Levels 5 to 16, including brackets	m	4,860	395.00	1,919,700.00
4.4.02	Horizontal sunshades to the serviced apartment balconies, Levels 17 to 28	m	2,140	445.00	952,300.00
4.4.03	Acoustic louvres to plant rooms, 300 mm deep	m2	640	980.00	627,200.00
4.4.04	Perforated metal screening to rooftop plant	m2	860	610.00	524,600.00
4.4.05	Bird deterrent spikes and mesh to fins and ledges	m	2,400	38.00	91,200.00
4.5	**SEALANTS, TESTING AND ACCESS**				
4.5.01	Silicone weather seals to all facade joints	m	18,600	24.50	455,700.00
4.5.02	Facade performance testing by an independent laboratory: air, water, structural and seismic tests on a full-size test panel	item	1	465,000.00	465,000.00
4.5.03	Site water tests to installed facade joints, 5% of joints	nr	120	1,350.00	162,000.00
4.5.04	Thermal and condensation analysis, with reports	item	1	95,000.00	95,000.00
4.5.05	Mast climbing work platforms to the podium facade	month	14	38,500.00	539,000.00
4.5.06	Facade cleaning on completion	m2	32,400	4.25	137,700.00
4.6	**DESIGN, MOCK-UP AND SUBMITTALS**				
4.6.01	Facade design development, shop drawings and structural calculations for every element in this Bill	item	1	985,000.00	985,000.00
4.6.02	Visual mock-up of one podium bay with granite cladding and a GRC screen	item	1	285,000.00	285,000.00
4.6.03	Samples, prototypes and material testing	item	1	64,000.00	64,000.00
4.6.04	Operation and maintenance manuals and warranties for the facade	item	1	38,000.00	38,000.00
	Carried forward				**37,776,472.50**

Item	Description	Unit	Qty	Rate (SAR)	Amount (SAR)
	Brought forward				**37,776,472.50**
4.7	**FACADE PRELIMINARIES**				
4.7.01	Facade subcontractor site establishment, offices and stores	month	18	24,500.00	441,000.00
4.7.02	Tower crane time allocated to facade installation	month	12	68,000.00	816,000.00
4.7.03	Facade engineer and installation supervisor on Site	month	18	32,000.00	576,000.00
4.7.04	Protection of the installed facade until handover	item	1	145,000.00	145,000.00
4.7.05	Temporary hoarding and protective gantries at street level during facade works	month	16	18,750.00	300,000.00
4.7.06	Removal of facade packaging and waste off Site	item	1	42,500.00	42,500.00
	Total carried to Summary				**40,096,972.50**