Al Khobar Coastal Logistics Park - Package 2

Bill of Quantities - External Works and Landscaping

Revision A | Issued 12 February 2026 | Contract No. KLP-P2-2026-007

Prepared by Rakeen Consulting Engineers for Bahr Line Industrial Development Company

All rates and amounts are in Saudi Riyals (SAR) and exclude Value Added Tax.

Rates include supply, delivery, installation, testing and protection. Quantities are measured net from the Drawings and are subject to remeasurement.

The total of this Bill is carried to the Contract Price.

Item	Description	Unit	Qty	Rate (SAR)	Amount (SAR)
X.1	**PERIMETER AND SECURITY**				
X.1.01	Perimeter fence, 2.4 m high welded mesh on steel posts, with concrete plinth	m	1,780	485.00	863,300.00
X.1.02	Motorised sliding vehicle gates, 12 m clear opening	nr	3	128,000.00	384,000.00
X.1.03	Gatehouse, 36 m2, complete with services and finishes	item	1	465,000.00	465,000.00
X.1.04	Vehicle barriers, bollards and crash-rated gate at the main entrance	item	1	118,000.00	118,000.00
X.2	**LANDSCAPING AND IRRIGATION**				
X.2.01	Imported topsoil, 300 mm deep, to planted areas	m2	14,500	32.00	464,000.00
X.2.02	Trees, 3 m to 4 m high, supplied, planted and staked	nr	420	1,850.00	777,000.00
X.2.03	Shrubs and ground cover planting, including maintenance for 12 months	m2	11,200	96.00	1,075,200.00
X.2.04	Drip irrigation network with controllers and valves	m2	14,500	48.00	696,000.00
X.2.05	Treated sewage effluent connection and irrigation storage tank	item	1	286,000.00	286,000.00
X.3	**EXTERNAL UTILITIES**				
X.3.01	Street lighting ducts and draw pits	m	4,600	118.00	542,800.00
X.3.02	Telecom ducts and chambers	m	4,600	96.00	441,600.00
X.3.03	Irrigation and potable water mains, HDPE, 110 mm to 315 mm	m	3,800	342.00	1,299,600.00
X.3.04	Signage, flagpoles and site furniture	item	1	164,000.00	164,000.00
	Total carried to Summary				**7,576,500.00**