SUBCONTRACT AGREEMENT

Structural Steel Frames for Warehouses W1 to W4

Subcontract No.	KLP-P2-SC-03
Main Contract	KLP-P2-2026-007, Al Khobar Coastal Logistics Park - Package 2
Contractor	Thuraya Build Contracting Company
Subcontractor	Sahel Steel Structures Factory
Date	10 May 2026

1 Parties

This Subcontract is made on 10 May 2026 between Thuraya Build Contracting Company ("the Contractor"), of Dammam Second Industrial City, Kingdom of Saudi Arabia, represented by Eng. Rami Haddad, Project Manager, and Sahel Steel Structures Factory ("the Subcontractor"), of Jubail Industrial City 2, Kingdom of Saudi Arabia, represented by Mr. Tariq Mansour, General Manager.

The Subcontract Works form part of the Works under Main Contract No. KLP-P2-2026-007 between the Contractor and Bahr Line Industrial Development Company. The Subcontractor has read the Main Contract and shall perform the Subcontract Works so that the Contractor is not in breach of it.

2 Subcontract Works

The Subcontract Works comprise:

- Connection design, shop drawings and fabrication drawings for the portal frames of Warehouses W1 to W4, for the Engineer's review.
- Supply of structural steel grade S355JR for the portal frames, eaves beams, gable posts, crane beams and bracing, about 3,150 tonnes in all.
- Fabrication, shot blasting and painting of the main members to the Specification, and hot-dip galvanising of the purlins and side rails.
- Delivery to Site in erection sequence, with mill certificates and inspection records for every batch.
- Erection, lining, levelling, bolting and grouting of the frames on the holding-down bolts cast in by the Contractor.
- Supply and fixing of purlins, side rails, sag rods and roof bracing, ready to receive the cladding.

Excluded from the Subcontract Works:

- Foundations, holding-down bolts and grout, which the Contractor supplies and casts in.
- Roof and wall cladding, roof lights, gutters and rainwater goods.
- Craneage beyond the Subcontractor's own mobile cranes, and the overhead travelling cranes of the warehouses.

3 Subcontract Price

The Subcontract Price is SAR 14,250,000.00 (Fourteen Million, Two Hundred and Fifty Thousand Saudi Riyals only), excluding Value Added Tax, for about 3,150 tonnes of fabricated and erected steel. The Price is a lump sum; it is adjusted only for variations instructed in writing by the Contractor.

4 Programme

The Subcontractor starts fabrication on 1 June 2026 and completes erection of each warehouse by the following dates:

Warehouse	Erection complete by
W1	15 November 2026
W2	31 January 2027
W3	31 March 2027
W4	30 April 2027

Completion of the whole of the Subcontract Works, with the purlins, side rails and bracing fixed on all four warehouses, is due by 30 April 2027.

5 Liquidated Damages

If the Subcontractor fails to complete the erection of any warehouse by its date, the Subcontractor pays the Contractor liquidated damages of SAR 7,500.00 per day of delay, up to 10% of the Subcontract Price in all.

6 Payment

The Subcontractor submits a monthly statement of the steel fabricated, delivered and erected. The Contractor pays within 30 days of its certificate, less retention of 10%, half of which is released on completion of erection of Warehouse W4 and the rest at the end of the Main Contract Defects Notification Period.

7 Quality and Safety

The Subcontractor works to the Main Contract Specification, Part 4 Structural Steel and Cladding, and to the Contractor's Health, Safety and Environment Plan. Every erection crew includes a certified rigger and a qualified crane operator, and no member is lifted without an approved lifting plan.

Signed for and on behalf of the parties

For the Contractor Eng. Rami Haddad, Project Manager, Thuraya Build Contracting Company

For the Subcontractor Mr. Tariq Mansour, General Manager, Sahel Steel Structures Factory